## BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

### DRAFT TENDER SCHEDULE

**Issued to :**

**Original / Duplicate**

**Name of the Work : Improvements of Roads from Muneswara Temple to Hosadevaramane in Jakkur village in ward no 07 Byataryanapura**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | **786.00** | KSRRB 300-47 Scarifying Kankar /gravel/ metal crust upto 150mm thick with power roller and scarifier , disposal of stuff including cost of labour charges HOM of | | **25.92** | |
| 2 | **65.52** | KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 1.5m, excavated surface | | 83.16 | |
| 3 | **786.00** | KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (148, I.No. | | **4.86** | |
| 4 | 78.60 | KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine | | 5070.6 | |
| 5 | **168.00** | KSRB5 25 providing and constructing non load bearing with cement concreate solid blocks with compresive strenth not less than 3.5 newtown per sqmm with cement mortor 1:4 with block of size 40X20 X20cms | | **1018.44** | |

| | | | | | |
|---|---|---|---|---|---|
| 6 | 78.60 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., | | 6332.04 | |
| 7 | **786.00** | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including | | 97.20 | |
| 8 | **37.50** | Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of | | 124.20 | |
| 9 | 77.76 | KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing | | 192.24 | |
| 10 | 15.12 | KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, | | 5070.60 | |
| 11 | **34.56** | KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in | | 4135.32 | |
| 12 | 898.33 | KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all | | 244.08 | |

| | | | | | |
|---|---|---|---|---|---|
| 13 | 25.92 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish | | 6332.04 | |
| 14 | 2.59 | KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per | | 69805.80 | |
| 15 | 67.20 | KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of20mm nicely lining, including | | 99.36 | |
| 16 | **143.28** | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km ( Page No.141) | | 72.71 | |
| | | | | | |

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ಧುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ಧುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ

22/12